

Round building parking lot - \$125,680

Remove Asphalt	12000	SF
Remove Base	533	CY
Install 12" Gravel Base	533	CY
Install 2 1/2" asphalt	12000	SF
Sidewalk	600	SF
Striping	1	LS

Maintenance Parking Area - \$247,584

Remove Asphalt	18000	SF
Remove Base	800	CY
Concrete Demo	1	LS
Install 12" Gravel Base	800	CY
Install 2 1/2" asphalt	18000	SF
Sidewalk	1380	SF
Curb and Gutter	170	LF
Approach	1	LS
Fence	390	LF
Gates	2	EA
Striping	1	LS

Elementary School - \$935,335

Remove Asphalt	45000	SF
Remove Base	2000	CY
Remove Sod	15000	SF
Concrete Demo	14000	SF
Install 12" Gravel Base	5244	CY
Install 2 1/2" asphalt	118000	SF
Retaining Wall	270	LF
Drywell and inlet	1	LS
Striping	1	LS

Engineering/Design-\$35,700

**Total-\$1,344,299**